

# INSTALLATION & MAINTENANCE INSTRUCTIONS 5213 SERIES



# 1) INTRODUCTION

The Altecnic 5213 Series (Ø 15 and 22 mm Models) thermostatic mixing valve has been specifically designed and manufactured to meet the requirements of BS 7942: 2000 and NHS D08. The valve has been independently tested and approved as a TYPE 3 valve under the TMV3 scheme.

## 2) TECHNICAL SPECIFICATION

Outlet Temp Adjustment Range  $30^{\circ}\text{C} \sim 50^{\circ}\text{C}$  Temperature Stability  $\pm 2^{\circ}\text{C}$  Max. Hot Inlet Temp  $85^{\circ}\text{C}$ 

Inlet Temperature Range 52°C ~ 65°C : Hot Supply 05°C ~ 20°C : Cold Supply

Max. Working Pressure

Min. Working Pressure

D08 Working Pressure Ranges

0.2 Name of the State Capping

10 Bar : Static

0.2 Bar : Dynamic

0.2 ~ 1.0 : Low Pressure

1.0 ~ 5.0 : High Pressure

Min Temp Differential (Mix to Hot) for fail-safe 10°C


Max. Pressure Inlet Differential 6:1

Max. Flow Rate @ 1 Bar Differential: - Ø 15 mm 1500 | / hour - Ø 22 mm 1700 | / hour

## 3) APPROVALS

TMV3 Scheme Approval Number ETC/190/1002-BC/074/0204
WRAS Scheme Approval Number 0210098
Build Cert Approval Number Details Available on Request


#### 4) DIMENSIONS



Code	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	Weight (Kg)
521315	135	67,5	105	49	56	0,50
521322	150	75	106	49	57	0,60
MX5315	191	96	105	49	56	0,65
MX5322	197	99	106	49	56	0,75

# 5) FAIL SAFE FUNCTION

The Altecnic 5213 series (15 mm & 22 mm Models) are designed to stop the mixed water flow in the event of either the hot or cold water supply failing when installed in accordance with these instructions. To ensure full closure of the mixed water flow the minimum temperature differential between the hot water inlet to the valve and the mixed water outlet **MUST be at least 10°C.** 



#### 7) TEMPERATURE SETTING

Ensure that the valve is commissioned under normal system conditions. The valve MUST be commissioned to suit site condition and the desired outlet temperature set by the installer.

With normal supply conditions established and the hot and cold water supplies running, open the outlet fitting and leave running.

Remove the cap and release the locking nut from the temperature spindle.

Rotate the spindle anti clockwise to increase the mixed water outlet temperature and rotate the spindle clockwise to decrease the mixed water outlet temperature using the cap until the required temperature is achieved.

We recommend the use of a digital thermostat when setting of the valve, once the desired outlet temperature is reached, re-fit the locking nut to the temperature spindle to prevent unauthorized adjustment of the valve and replace the cap on the valve body.





## 8) APPLICATION

The Altecnic 5213 series (15 mm & 22 mm Models) thermostatic mixing valve has been independently tested by WRc and certified as meeting the requirements of the NHS DO8 specification under the TMV3 Scheme as being suitable for use on the following designations.

Application	Range	Application	Range
Basin	High Pressure	Basin	Low Pressure
Bidet	High Pressure	Bidet	Low Pressure
Shower	High Pressure	Shower	Low Pressure
Bath (T44)*	High Pressure		
Bath (T46)* High Pressure		* 22 mm only	


## 9) INSTALLATION

IMPORTANT- The following instructions must be read prior to the installation of an Altecnic 5213 series (15 mm & 22 mm Models valve). The installer should also be aware of his responsibility and duty of care to ensure that all aspects of the installation comply with all current regulations and legislations.

It has been brought to our attention that flushing through water systems using certain chemicals may wholly or partially remove the lubricant from the internal workings of the valve, which may adversely effect its performance. We recommend that following flushing of the system with chemicals, valves are checked for correct operation.

- 9.1 It is essential that, before installing a Altecnic 5213 series (15 mm & 22 mm Models) valve, the supply conditions of the system to which the valve is intended to be fitted are checked to confirm compliance with the parameters as quoted within section 2 and conditions on which the approval is granted i.e. verify supply temperatures, supply pressures, risk assessments etc.
- 9.2 Consideration must be made for the possibility of multiple / simultaneous demands being made on the supply system whilst the Altecnic 5213 series (15 mm & 22 mm Models) is in use, all practical precautions must be made to ensure that the valve is not affected. Failure to make provision within the pipe sizing etc will affect the performance of the Altecnic 5213 series (15 mm & 22 mm Models).
- 9.3 The supply system to which the Altecnic 5213 series (15 mm & 22 mm Models) valve is to be installed into must be thoroughly flushed and cleaned to remove any debris, which may be accumulated during the installation. Failure to remove any debris will affect the performance and the manufacturer's warranty on the product. Independent filters / check valves and isolation valves must be fitted in conjunction with the valve. In areas that are subject to aggressive water, provision must be made to treat the supplies prior the supplies entering any Altecnic product.
- 9.4 The maximum flow rate of the valve will only be achieved when the supply conditions are achieved as quoted within section 2, with a flow condition under 1 bar differential pressure.
- 9.5 Altecnic 5213 series (15 mm & 22 mm Models) valve has been designed to ensure that the valve can be installed in any position whether vertical or horizontal, it can be surface mounted or within a supply duct. It is essential that the access to the valve be not obstructed for future maintenance that may be required to the valve or associated fittings.
- 9.6 We recommend that the Altecnic 5213 series (15 mm & 22 mm Models) fail-safe thermostatic mixing valve is installed as close as practically possible to the outlet(s) which it is serving. In this situation attention must be paid to the maximum distance of pipework from the mixed water outlet of the valve to any terminal fitting, as recommended by NHS Estate's.

- 9.7 The connecting hot and cold water supplies must be connected to the valve strictly in accordance with the indications on the body of the valve i.e. hot water supply to the hot port of the valve.
- 9.8 In a situation where one or both the water supplies are excessive, it is possible to fit an Altecnic Pressure Reducing Valve WRAS approved product to reduce the pressure(s) to within the limits as quoted previously.
- 9.9 Any thermostatic mixing valve must be fitted with a back flow prevention device, such as check valves, to prevent the cross contamination of supplies. The Altecnic 5213 series (15 mm & 22 mm Models) is complete with integral insert check valves and strainers, however if required additional WRAS approved back flow prevention devices should be used. Altecnic have full range of back flow prevention devices available on request to complement this product.
- 9.10 We recommend that Y Pattern strainers and full bore isolation valves are installed in conjunction with the Altecnic 5213 series (15 mm & 22 mm Models) fail safe Thermostatic Mixing Valve as close as practically possible to the location of the valve.
- 9.11 It is essential that the Altecnic 5213 series (15 mm & 22 mm Models) fail-safe Thermostatic Mixing Valve should not be installed in situations where there is a possibility of the valve being deprived of water or where demands for water are greater than the actual stored supplies.
- 9.12 To ensure that the performance levels of the Altecnic 5213 series (15 mm & 22 mm Models) valve is maintained (in the event of cold water failure), the temperature of the hot water supply at the point of entry to the valve must be a minimum of 10°C above the commissioned mixed water discharge temperature.
- 9.13 The Altecnic 5213 series (15 mm & 22 mm Models) fail-safe Thermostatic Mixing Valves must not be subject to any extreme temperature variations either during the installation or under normal operating conditions.



#### 10) COMMISSIONING

IMPORTANT - The following instructions must be read and understood prior to the commissioning of an Altecnic 5213 series (15 mm & 22 mm Models) fail-safe thermostatic mixing valve. If under any circumstances there are aspects to the installation / system which do not comply with the specification laid down, the valve MUST NOT be put into operation until the system / installation compiles with our specification.

- 10.1 Ensure that the system is thoroughly cleaned and free from any debris prior the commissioning of the Altecnic 5213 series (15 mm & 22 mm Models) fail-safe Thermostatic Mixing Valve.
- 10.2 The commissioning of the temperatures must be carried out using a suitably calibrated thermometer - preferably a digital thermometer.
- 10.3 In the absence of other temperatures being specified, we recommend that the outlet temperatures quoted in table 1 are used.

TABLE 1

Application	Recommended Set Mixed Water Temperature
Wash Hand Basin	41°C
Shower	41°C
Bidet	38°C
Bath Unassisted*	44°C
Bath Assisted*	46°C

<sup>\* 22</sup> mm only

"Extracted from the National Health Service - Health Guidance Note - Safe Hot Water and Surface Temperatures"

- 10.4 Each Valve must be commissioned taking into consideration any fluctuations, which may occur within the system due to simultaneous demands. It is advisable that any outlets which are connected to the same supply as the mixing valve is connected to, are opened during the setting of the mixed water temperature. During commissioning it is advisable to ensure that the water temperatures are established before any attempt to commission.
- 10.5 Once the supply temperatures are stable and the normal operating conditions are established, the valve can be commissioned.

Due to the unique design of the head, the temperature setting can be adjusted by removing the head from the valve body and reversing the head onto the temperature adjustment spindle. We suggest that the following sequence is followed when commissioning the valve:

- a) Set the mixed water temperature to the required temperature
- b) Measure and record the temperature of the hot and cold water supplies at the connections to the valve.
- c) Measure and record the temperature of the water discharging from the valve from the largest and smallest draw off point.
- d) Isolate the cold water supply to the valve and monitor the mixed water temperature.
- e) Measure and record the maximum mixed water temperature and the final temperature. The final temperature found during the test should not exceed the values quoted in table 2.

## TABLE 2

Application	Maximum Mixed Water Temperature
Wash Hand Basin	43°C
Shower	43°C
Bidet	40°C
Bath Unassisted*	46°C
Bath Assisted*	48°C

<sup>\* 22</sup> mm only

- f) Record all the equipment used during the commissioning
- 10.6 Once the desired temperature is established, remove the head and secure the temperature spindle with the locking nut and replace the head into its original position to the prevent tempering by unauthorized persons.
- 10.7 Ensure that the application, to which the valve will be used in, is appropriate for the approved designation.

The above information must be recorded and updated on every occasion when any work is carried out on the valve.

## 11) MAINTENANCE


To ensure that the Altecnic 5213 series (15 mm & 22 mm Models) valve maintains a high level of protection, we advise the following in service testing is followed (the same equipment used to commission the valve initially must be used in the following tasks).

- 11.1 After a period of between 6 and 8 weeks after commissioning, carry out the following.
  - a) Record the temperature of the hot and cold water supplies.
  - b) Record the temperature of the mixed water at the largest draw off flow rate
  - c) Record the temperature of the mixed water at the smallest draw off flow rate
- 11.2 If the mixed water temperature has changed significantly from the previous test results (e.g. > 1 K), record the change and before re-setting the mixed water temperature check that:
  - a) All the strainers are clean (see 9.10)
  - b) All the check valves are in good working order (see 9.9)
  - c) The isolation valves are fully open
- 11.3 If the mixed water temperature is acceptable, carry out the following:
  - a) Record the temperature of the hot and cold water supplies
  - b) Record the temperature of the mixed water at the largest draw off flow rate
  - Record the temperature of the mixed water at the smallest draw off flow rate
  - d) Isolate the cold water supply to the mixing valve and monitor the mixed water temperature
  - e) Record the maximum temperature achieved as a result of (d) and the final temperature (the final temperature should not exceed the values quoted in table 2)
  - f) Record the equipment used during these tests
- 11.4 If in the test during 11.3.e the mixed water temperature is greater then the values quoted in table 2 or the maximum temperature exceeds the corresponding values from previous test results by more than 2 K, the valve must be serviced.
- 11.5 After a period of between 12 and 15 weeks after commissioning, carry out the sequence of tests as described in 11.1, 11.2, 11.3 and 11.4.
- 11.6 Dependant upon the results obtained from the first two series of tests, there are a number of possible outcomes:
  - a) If no significant change in the mixed water temperatures (e.g. < 1 K) is recorded between commissioning and 11.1 or between commissioning and 11.5 - the next in service testing should be carried out at a period of 24 to 28 weeks after initial commissioning.
  - b) If a small change (e.g. 1 2 K) in the mixed water temperature is recorded in only one of these periods, necessitating adjustment of the mixed water temperature, then the next in service test can be deferred to 24 to 28 weeks after commissioning.
  - c) If small changes (e.g. 1 2 K) in the mixed water temperature are recorded in both of these periods, necessitating adjustment of the mixed water temperature, then the next in service test can be deferred to 18 to 21 weeks after commissioning.
  - d) If significant changes (e.g. > 2 K) in the mixed water temperature are recorded in both of these periods necessitating service work, then the next in service test should be carried out at 18 - 21 weeks after commissioning.

- 11.7 The general principle to be observed after the first 2 or 3 inservice tests is that the intervals of future test should be set to those which previous tests have shown can be achieved with no more than a small change in mixed water temperature.
- 11.8 In all areas periodic maintenance of the valve and associated fittings i.e. strainers, check valves will ensure optimum performance levels are maintained.
- 11.9 The inlet strainers on both the hot and cold water supply inlet can be removed for cleaning by unscrewing the inlet union nuts and carefully pulling apart the connecting pipework.
- 11.10 The built in check valves can be accessed in a similar way to 11.9 to ensure freedom and correct seating.

# 12) SPARES;

A full range of spare are available for this product from Altecnic. PLEASE NOTE: Only genuine spares should be used



### 13) PROBLEM SOLVING

The following details are supplied for on site queries, should you require any further assistance our technical department can be contacted directly on Tel - 01889 207200

# 13.1 Hot Water at the cold tap(s)

- Operation of the insert check valve is hindered; check if the valve is sealing correctly
- ii. Check valves not fitted
- iii. Unbalanced hot/cold supply pressures

# 13.2 Fluctuating mixed water temperature

- i. Erratic supply temperatures at the inlets of the valve
- ii. Starvation of the water supplied at the inlets of the valve
- iii. Incorrect commissioning of the valve

#### 13.3 Erratic Flow from the valve

- i. Insufficient water supplies
- Fluctuations in the supply pressures/temperatures
- iii. Adverse effect created by other draw off points on the system

#### 13.4 No Flow / reduced flow from the valve

- i. In line strainer are blocked
- ii. Insufficient supply pressure
- iii. Debris obstructing valve operation
- valve requires servicing (service kit available from your local stockiest)

#### 13.5 Valve does not fail safe when tested

- Installation not in accordance with or recommendations.
- ii. The minimum temperature differential not achieved
- iii. Internal mechanism hindered by debris



Altecnic Ltd Mustang Drive, Stafford, Staffordshire ST16 1GW T: 01785 218200 F: 01785 218201 E: sales@altecnic.co.uk